

	R-S Single Fa	mily Residential	1	
Requirements		Existing	Proposed	Varian
Lot Area	7,500 sf	8,185 sf	8,185 sf	No
Lot Width	75 ft	70.0 ft	70.0 ft	No*
Setbacks				
Front Yard	25 ft	25.8 ft	25.8 ft	No
Side Yard	15%(LW)) 10.5 ft	10.1 ft/7.1 ft	10.1 ft/7.1 ft	Yes*
Comb. Side Yard	30%(LW) 21.0 ft	17.2 ft	17.2 ft	Yes*
Rear Yard	25 ft	43.0 ft	43.0 ft	No
Bldg. Hgt.	35 ft	27.3 ft	35.0 ft	No
Lot Coverage	40%	3014 sf/36.8%	3349 sf/40.9%	Yes
Bldg. Coverage	25%	2111 sf/25.8%	2426 sf/29.64%	Yes*





335.00'

PROP. DRIVEWAY-EXPANSION



BUILDING HEIGHT CALCULATION N.T.S.





## TYPICAL REINFORCED WALL SECTION


Keystone Compac II Unit or Equivalent N.T.S.


Net Soil Removed from Site

## LOT COVERAGE CALCULATIONS PROPOSED

EXISTING DWELLING COV. PORCH TOTAL	1873 sf 238 2111 sf = 25.8%	PROPOSED DWELLING COV. PORCH TOTAL	$ \begin{array}{r} 2212 \text{ sf} \\ \underline{214} \\ 2426 \text{ sf} = 29.64\% \end{array} $
FRONT WALK DECK GRAVEL AREA DECK STEPS SPORTS COURT DRIVEWAY TOTAL	97 sf 207sf 29 sf 38 sf 0 sf(916) 532 sf 3014 sf = 36.8%	FRONT WALK REAR LANDING DECK/LANDING PATIO DECK STEPS ELEVATED WALK SPORTS COURT DRIVEWAY TOTAL	0 sf(97) 0 sf(29) 266 sf 0 sf(216) 24 sf 120 sf 0 sf(916) 513 sf 3349 sf = 40.9%

**BLOCK** 





- NON-WOVEN GEOTEXTILE


" REINFORCED ONC. COVERS

1000 GALLON SEEPAGE PIT DETAIL

=	
Addition	
Foundation 50 L.ft	
(50 ft)(4.5)(4.5)	38 cu yds cut
Backfill (2/3)(38)	25 cu yds fill
1000 Gal. Seepage Pits	54 cu yds cut
	10 cu yds fill
Total Cut	92 cu yds cut
Total Fill	35 cu yds fill

57 cy yds

Soil Moving Requirements



Z

PROP. PERMEABLE
PAVER WALKWAY

REVISED 6-22-23 SPORT COURT MATERIAL, DETAIL REVISED 2-24-23 COVERED PORCH, ZONING & COVERAGE REVISED 5-25-22 ELEVATED WALK

## NOTES:

- 1. Applicant:
- 2. Property address:3. Property known as
- Teaneck NJ. in accordance with the Tax
- Assessment Map of the Township of Teaneck.
  4. Property is located in the R-S Single Family Residential Zone.
- 5. Elevations based on an assumed datum.
- 6. Existing spot elevations indicated with an X. Proposed spot elevations in [ ]. 7. Underground utility locations to be verified in the field prior to
- commencement of construction.
- 8. Existing utility connections are to be inspected. If same are not in acceptable condition, new service connections shall be installed in accordance with Township specifications.
- 9. The applicant shall be responsible for the replacement of any curbing, sidewalk or pavement damaged or destroyed as a result of construction activities on this site.
- 10. Survey and topography performed by this office, on 9/30/21.
- 11. A roof height check will be performed at the time of framing.

DRAINAGE CALCULATIONS					
10 Yeo	10 Year Storm (I=2"/hr., 60 min. duration)				on)
					•
Runoff Coef			Area		CIA
Dwelling, Porch	.99	2426 sf	0.058	Acres	0.114 cfs
Volume = $(60*Qpeak)(60)$ Volume = $409.7$ CF = $3,065$ Gallons					
Minimum Storage Required: 3,065 Gallons					
Storage Provided:	2 >	( 1923 =	3,846 Gall	ons	
		_			

Scale: 1"=20'	*	CERTIFIED TO:
DATE: OCTOBER 20, 2021		SERVINIES 10.
PARTY: DR/JN	Township of Township Downson Country N. I.	
PREPARED BY: CJL	Township of Teaneck, Bergen County, N.J.	
DRAWN BY: SPM	PROPERTY SITUATED IN THE TOWNSHIP OF TEANECK, BERGEN COUNTY, NEW	
	JERSEY.	
FILE No. SPI306MERC	MAP SOURCE: TAX ASSESSMENT MAP OF THE TWONSHIP OF TEANECK, BERGEN COUNTY, NEW JERSEY.	